



Tentative Interim Amendment

NFPA[®] 70[®]

National Electrical Code[®]

2017 Edition

Reference: 590.4(G)

TIA 17-4

(SC 17-4-2 / TIA Log #1244)

Pursuant to Section 5 of the NFPA *Regulations Governing the Development of NFPA Standards*, the National Fire Protection Association has issued the following Tentative Interim Amendment to NFPA 70[®], *National Electrical Code*[®], 2017 edition. The TIA was processed by the National Electrical Code Panel 3 and the NEC Correlating Committee, and was issued by the Standards Council on April 5, 2017, with an effective date of April 25, 2017.

A Tentative Interim Amendment is tentative because it has not been processed through the entire standards-making procedures. It is interim because it is effective only between editions of the standard. A TIA automatically becomes a public input of the proponent for the next edition of the standard; as such, it then is subject to all of the procedures of the standards-making process.

1. Revise 590.4(G) to read as follows:

590.4(G) Splices. A box, conduit body, or other enclosure, with a cover installed, shall be required for all splices, ~~except where:~~

Exception: On construction sites, a box, conduit body, or other enclosure shall not be required for either of the following conditions:

- (1) The circuit conductors being spliced are all from nonmetallic multiconductor cord or cable assemblies, provided that the equipment grounding continuity is maintained with or without the box.
- (2) The circuit conductors being spliced are all from metal sheathed cable assemblies terminated in listed fittings that mechanically secure the cable sheath to maintain effective electrical continuity.

Issue Date: April 5, 2017

Effective Date: April 25, 2017

(Note: For further information on NFPA Codes and Standards, please see www.nfpa.org/docinfo)

Copyright © 2017 All Rights Reserved
NATIONAL FIRE PROTECTION ASSOCIATION